## **TRANSFORMER- 2000 KVA CROMTON**

Supplying, receiving, erection, testing & commissioning of 2000 KVA 11/0.433 KV, outdoor type, oil cooled 3 Phase, 4 wire 50Hz, with On load tap changer, +5% to -7%, 2.5% per step with cable box at primary and at secondary end for outdoor installation, winding temperature indicator, restricted earth fault CT, buchholz relay, silica breather, MOG with contacts, Marshal box to connect control cable between HT panel and transformer as per specification etc. as required. 01 SET

ACB ISOLATOR PANEL 3200 AMP, 50KA, 415 volt 4-P MDO ACB Isolator panel 01 SET

H.T. CABLES

Supply, laying, testing and commissioning of 11KV 3C x 300 sqmm (E) XLPE cable 20 MTRS

## **HT CABLE TERMINATIONS**

Suppy and erection of indoor heat shrink type terminations for 3c x 300sqmm XLPE 11KV cable 02 SETS

Supply & installation of following sizes of 1.1 KV grade XLPE insulated aluminium/copper conductor, inner & outer PVC sheath armoured power cables

3.5c x 300sqmm Alm, XLPE, arm 1071 RM 2c x 2.5 sqmm multistranded copper, PVC, arm 40 RM 4c x 2.5 sqmm multistranded copper, PVC, arm 40 RM 12c x 2.5 sqmm multistranded copper, PVC, arm 40 RM

Supply and making terminal joints for the following sizes of 1.1 KV XLPE insulated, Aluminium conductor armoured cable including providing terminal aluminium lugs, crimping the joints effecting terminal connections to the equipment complete as required double brass compression gland.

3.5c x 300sqmm Alm, XLPE, arm14 set2c x 2.5 sqmm multistranded copper, PVC, arm02 set4c x 2.5 sqmm multistranded copper, PVC, arm02 set12c x 2.5 sqmm multistranded copper, PVC, arm02 set

Supply,installation,testing and comissioning of advance Maintenance Free Chemical Gel Earthing of Single Pipe Technology - with 3 mtr long 80 mm dia GI pipe (Class-B), filled with highly conducting metallic compounds with the permenant sealings at the both the ends with the lead terminal 50x6mm copper strip from top to bottom along with 50 Kgs chemical compound (Moisture Booster) to retain the moisture. (For Neutrals). 02 set

Supply,installation,testing and comissioning of advance Maintenance Free Chemical Gel Earthing of Single Pipe Technology - with 3 mtr long 80 mm dia GI pipe (Class-B), filled with highly conducting metallic compounds with the permenant sealings at the both the ends with the lead terminal 50x6mm GI strip from top to bottom along with 50 Kgs chemical compound (Moisture Booster) to retain the moisture. (For Body). 02 set

**Please send your quotations on email** <u>policehousingsociety@gmail.com</u> For further details, please contact: Police Officers Multi-State Co-operative Housing Society Ltd. Office Complex, PTS, Malviya Nagar, New Delhi-110017 Tel: 011-20861735, 9211140333